Tender Number: BBMP/2021-22/OW/WORK_INDENT48408

Schedule-B

Tender Name: Improvement to drain all around the parks at Bagalgunte ward no.14 in Dasarahalli Zone ward No.14

SNo	Item Name	Unit	Estimate Quantity	HONNAPPA MURTHY		
				Quoted Rate	Amount(in fig)	Amount(in words)
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1) -- -- All terms and conditions are as per tender document.	Cum	1443.58	281	405645.98	Rupees Four Lakh(s) Five Thousand Six Hundred Forty Five And Paise Ninety Eight Only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 - with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P 13, I 4.3) ---- All terms and conditions are as per tender document.	Cum	283.43	5900	1672237.00	Rupees Sixteen Lakh(s) Seventy Two Thousand Two Hundred Thirty Seven Only
3	Providing and laying plain/ reinforced cement concrete for side drains using M20 nomial mix concrete with OPC cement @ 300kgs, with 20mm and down size granite metal coarse aggregates @0.69cum and fine aggregates @0.43cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc, complete excluding cost of stell as per MORTH specification NO. 1500, 1700, 2200. Including cost of materials, labour, HOM complete as per specifications. Item No. 37.59.2/ page no:271/PWD SR 2018-19 ---- All terms and conditions are as per tender document.	Cum	455.51	7790	3548422.90	Rupees Thirty Five Lakh(s) Forty Eight Thousand Four Hundred Twenty Two And Paise Ninety Only
4	KSRRB - 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specification(P.No.18, I.No.4.46.2 S.R 2018-19) ---- All terms and conditions are as per tender document.	MT	26.37	97275	2565141.75	Rupees Twenty Five Lakh(s) Sixty Five Thousand One Hundred Forty One And Paise Seventy Five Only
5	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate) ---- All terms and conditions are as per tender document.	Sqm	1008.99	2453	2475052.47	Rupees Twenty Four Lakh(s) Seventy Five Thousand Fifty Two And Paise Forty Seven Only

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division Bangalore-57

SRI HONNAPPA MURTHY

Scanned with OKEN Scanner

No	Item Name	Unit	Estimate Quantity	HONNAPPA MURTHY		
				Quoted Rate	Amount(in fig)	Amount(in words)
6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge ---- All terms and conditions are as per tender document.	Sqm	135	5685	767475.00	Rupees Seven Lakh(s) Sixty Seven Thousand Four Hundred Seventy Five Only
7	5.29(b) Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete. Page No. 27/ Item No. 5.30/ PWD SR 2018-19 ---- All terms and conditions are as per tender document.	Nos	2492	455	1133860.00	Rupees Eleven Lakh(s) Thirty Three Thousand Eight Hundred Sixty Only
8	KSRB 800-1 Providing two coats after filling the surface with synthetic enamel paint in approved shades on new plastered surfaces, with materials, labour, complete as per specifications. MORTH chapter 8. (P.No.180, I.No.24.1 of PW, P&IWTD SR 2018-19) ---- All terms and conditions are as per tender document.	Sqm	392.38	85	33352.30	Rupees Thirty Three Thousand Three Hundred Fifty Two And Paise Thirty Only
	Total Amount				**12601187.40**	

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division Bangalore-57

SRI HONNAPPA MURTHY

Scanned with OKEN Scanner